



Rig 363 Inventory

(Nomac Rig 63)

DRAWWORKS:

LeTourneau LDW750K 1500 HP
Powered by (2) GE 1150 HP – AC motors

MAST:

Process Manufacturing 142'
750,000 lbs SHL on 12 Lines

SUBSTRUCTURE:

Process Manufacturing Box-on-Box
2-box w/ 21'6" floor height
750,000 lbs rotary w/ 500,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK HOOK: National Oilwell 650G500,
500 ton

ROTARY TABLE:

National Oilwell C-275 Independent Drive
Powered by (1) 1150 HP – AC motor

DRIVE SYSTEM:

Omron 3 x 6 AC VFD
Highline Power Capabilities

ENGINE/GENERATORS:

3 - Caterpillar 3512C / Kato 1365kW
generators

Control System:

Omron 3 x 5 AC drive w / High Line
capability

MUD PUMPS:

2 - LeTourneau WH-1612, 1600 HP,
7500 PSI
Each powered by (1) GE 1500 HP – AC
motor

MUD SYSTEM:

2 tank, 1000 Bbl w/ 100 Bbl pre-mix included
w/ pit roofs

SOLIDS CONTROL EQUIPMENT:

SHAKERS:
2 - Derrick FLC-504

DEGASSER:
National DG-12

DESANDER:
National DSN-2V-10CTX

DESILTER:
National DSLR-16GG-4CTX

BOP EQUIPMENT:

ANNULAR:
Shaffer Style Spherical 13-5/8" – 5K WP

DOUBLE:

Cameron Type U 13-5/8" – 10K WP

SINGLE:

Cameron Type U 13-5/8" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

CAD Controls 6 station, 200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck: Varco ST-80C

Water Tank: 500 Bbl

Fuel Tank: 14,000 gallons

Trip Tank:
100 Bbl

Hyd. Hoists:
2 - Braden PD12C

Air Hoists:
1 - Ingersoll Rand K6U

Pipe Spinner:
Gray Mark 20

Wireline Machine:
Millennium Surveyor

EDR:
MD Totco

Hydraulic Catwalk:
Canrig PC-3000

TOP DRIVE:

NOV TDS-11, 500 ton

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Requested

OPTIONAL EQUIPMENT:

Rig Walking System available