



Rig 714 Inventory

(Nomac Rig 359)

DRAWWORKS:

Ideco 900E 1000 HP
Powered by (2) GE 752 motors

AUXILIARY BRAKE:

Elmagco 6032

MAST:

Lanzhou 142' x 21'
750,000 lbs SHL on 12 lines

SUBSTRUCTURE:

Major Rig Box-on-Box
3-box w/ 25' floor height
750,000 lbs rotary w/ 560,000 lbs
setback

TRAVELING EQUIPMENT:

BLOCK HOOK:
Ideco UTB 360, 360 Ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Ross Hill 4 x 4 SCR Model 1400

ENGINE/GENERATORS:

4 - Caterpillar 3508C / Kato 902kW
generators

MUD PUMPS:

2 - Emsco FB1600, 1600 HP, **7500 PSI**
Powered by (2) GE 752 motors

MUD SYSTEM:

2 tank, 1,050 Bbl

SOLIDS CONTROL EQUIPMENT:

SHAKERS: 3 - Derrick FLC-503

BOP EQUIPMENT:

ANNULAR:
Shaffer Spherical type 13-5/8" – 5K WP

DOUBLE:

Cameron Type U 13-5/8" – 10K WP

SINGLE:

Cameron Type U 13-5/8" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

Advanced Pressure 6 station,
200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:

500 Bbl

Fuel Tank:

15,000 gallons

Air Hoists:

1 - Ingersoll Rand K5UL
1 - Ingersoll Rand K6UL

Wireline Machine:

Five Star

EDR:

MD Totco

TOP DRIVE:

NOV TDS-11, 500 Ton

HYDRAULIC CATWALK:

Canrig PC3000

WALK / SKID:

1 - Rig Walking System

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Required