



Rig 719 Inventory

(Nomac Rig 19)

DRAWWORKS:

Oilwell 760E 1000 HP
Powered by (1) GE 752 High Torque Motor

AUXILIARY BRAKE:

Wichita 236

MAST:

Dreco 145'
600,000 lbs SHL on 10 lines

SUBSTRUCTURE:

Dreco Box-on-Box
2-box w/ 21'6" floor height
600,000 lbs rotary w/ 360,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK HOOK: National Oilwell 545G350,
350 ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Ross Hill 3 x 4 SCR Model 1400

ENGINE/GENERATORS:

3 - Caterpillar 3512B / Kato 1365kW
generators

MUD PUMPS:

2 - National Oilwell 10-P-130, 1300 HP
Each powered by (1) GE 752 High Torque
Motor

MUD SYSTEM:

2 tank, 1000 Bbl w/ 100 Bbl pre-mix
included
w/ pit roofs

SOLIDS CONTROL EQUIPMENT:

SHAKERS:
2 - Mi Swaco Mongoose PT

DEGASSER:

National D-1000-C

DESANDER:

National DSN-2V-10CTX

DESILTER:

National DSLR-16GG-4CTX

BOP EQUIPMENT:

ANNULAR:
Shaffer Style Spherical 11" – 5K WP

DOUBLE:

Cameron Type U 11" – 10K WP

SINGLE:

Cameron Type U 11" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

Advanced Pressure 6 station, 180 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:

2 - 500 Bbl each

Fuel Tank:

14,000 gallons

Trip Tank:

100 Bbl

Hyd. Hoist:

1 - Braden PD12C

Air Hoist:

1 - Ingersoll Rand K5U

Pipe Spinner:

Gray Mark 20

Wireline Machine:

Millennium Surveyor

EDR:

MD Totco

TOP DRIVE:

NOV TDS-11, 500 ton

MULTI-WELL PAD SITE:

Beam Rail Skidding System
Capabilities: 120'

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Required