



## Rig 720 Inventory

(Nomac Rig 20)

**DRAWWORKS:**

Oilwell 760E 1000 HP  
Powered by (1) GE 752 High Torque Motor

**AUXILIARY BRAKE:**

Wichita 236

**MAST:**

Dreco 145'  
600,000 lbs SHL on 10 lines

**SUBSTRUCTURE:**

Dreco Box-on-Box  
2-box w/ 21'6" floor height  
600,000 lbs rotary w/ 360,000 lbs setback

**TRAVELING EQUIPMENT:**

BLOCK: Emsco RA-44-5, 350 ton  
HOOK: Web Wilson 350 ton

**ROTARY TABLE:**

National Oilwell C-275

**DRIVE SYSTEM:**

Ross Hill 3 x 4 SCR Model 1400

**ENGINE/GENERATORS:**

3 - Caterpillar 3512B / Kato 1365kW  
generators

**MUD PUMPS:**

2 - National Oilwell 10-P-130, 1300 HP  
Each powered by (1) GE 752 High Torque  
Motor

**MUD SYSTEM:**

2 tank, 1000 Bbl w/ 100 Bbl pre-mix  
included  
w/ pit roofs

**SOLIDS CONTROL EQUIPMENT:**

SHAKERS:  
2 - Mi Swaco Mongoose PT

DEGASSER:

National D-1000-C

DESANDER:

National DSN-2V-10CTX

DESILTER:

National DSLR-16GG-4CTX

**BOP EQUIPMENT:**

ANNULAR:  
Shaffer Style Spherical 11" – 5K WP

DOUBLE:

Cameron Type U 11" – 10K WP

SINGLE:

Cameron Type U 11" – 10K WP

**CHOKE MANIFOLD:**

4" x 3" 10000 PSI

**CLOSING UNIT:**

Advanced Pressure 6 station, 180 gallon

**AUXILIARY EQUIPMENT:**

Iron Roughneck:  
Varco ST-80C

Water Tank:

2 - 500 Bbl each

Fuel Tank:

14,000 gallons

Trip Tank:

100 Bbl

Hyd. Hoist:

1 - Braden PD12C

Air Hoist:

1 - Ingersoll Rand K5UL

Pipe Spinner:

Gray Mark 20

Wireline Machine:

Millennium Surveyor

EDR:

MD Totco

**TOP DRIVE:**

NOV TDS-11, 500 ton

**MULTI-WELL PAD SITE:**

Beam Rail Skidding System  
Capabilities: 120'

**TUBULARS:**

Drill Pipe: 18,000' 5"  
Drill Collars: As Required