



## Rig 723 Inventory

(Nomac Rig 2)

### DRAWWORKS:

610 UE National 750 HP  
Powered by (1) GE 752 motor

### AUXILIARY BRAKE:

Parmac SSR-28

### MAST:

Dreco 145'  
600,000 lbs SHL on 12 lines

### SUBSTRUCTURE:

Dreco Box-on-Box  
2-box w/ 22' floor height

### TRAVELING EQUIPMENT:

BLOCK HOOK: Continental Emsco R-44,  
350 ton

### ROTARY TABLE:

National Oilwell C-275

### DRIVE SYSTEM:

Ross Hill 3 x 4 SCR Model 1400

### GENERATORS:

3 - Caterpillar 3508 / Kato 902kW generators

### MUD PUMPS:

2 - National Oilwell 10-P-130, 1300HP  
Each powered by (1) GE 752 motor

### MUD SYSTEM:

2 tank, 1200 Bbl w/ 100 Bbl pre-mix  
included

### SOLIDS CONTROL EQUIPMENT:

SHAKERS:  
2 - Mi Swaco Mongoose PT

DEGASSER:  
National DG-12

DESANDER:  
National DSN-2H-10CTX

DESILTER:  
National DSLR-16GG-4CTX

### BOP EQUIPMENT:

ANNULAR:  
Shaffer Style Spherical 11" – 5K WP

### DOUBLE:

Cameron Type U 11" – 5K WP

### CHOKE MANIFOLD:

4" x 3" 10000 PSI

### CLOSING UNIT:

ValvCon 7 Station, 135 gallon

### AUXILIARY EQUIPMENT:

Iron Roughneck:  
Varco ST-80C

Water Tank:  
2 - 500 Bbl each

Fuel Tank:  
14,000 gallons

Trip Tank:  
100 Bbl

Air Hoists:  
1 - Ingersoll Rand K6U  
1 - Ingersoll Rand K5UL

Pipe Spinner:  
Gray Mark 20

Wireline Machine:  
Oil Works 1600

Auto Driller:  
Satellite

EDR:  
MD Totco

TOP DRIVE:  
NOV TDS-11, 500 ton

HYDRAULIC CATWALK:  
Forum Wrangler 3550

### TUBULARS:

Drill Pipe: 18,000 of 5"  
Drill Collars: As requested