



Rig 724 Inventory

(Nomac Rig 240)

DRAWWORKS:

National 610-E 750 HP
Powered by (1) GE 752 motor

AUXILIARY BRAKE:

Baylor 19RD130W

MAST:

Dreco 142'
550,000 lbs SHL on 10 lines

SUBSTRUCTURE:

Dreco Box-on-Box
2-box w/ 20' floor height
600,000 lbs rotary w/ 350,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK: Ideco UTB-265-5-36, 265 ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Ross Hill 3 x 4 Model 1400
Highline Power Capabilities

ENGINE/GENERATORS:

3 - Caterpillar 3512C / Kato 1365kW
generators

MUD PUMPS:

2 - National Oilwell 10-P-130, 1300 HP
Each powered by (1) GE 752 motor

MUD SYSTEM:

3 tank, 1000 Bbl w/ 100 Bbl pre-mix
included

SOLIDS CONTROL EQUIPMENT:

SHAKERS:
2 - Mi Swaco Mongoose PT

DEGASSER:

National D-1000-C

DESANDER:

2 - National DSN-2V-CTX

BOP EQUIPMENT:

ANNULAR:
Shaffer Style Spherical 11" – 5K WP

DOUBLE:

Cameron Type U 11" – 10K WP

SINGLE:

Cameron Type U 11" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

Burnsco 5 station, 110 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:

500 Bbl

Fuel Tank:

14,000 gallons

Trip Tank:

100 Bbl

Hyd. Hoist:

Braden PD12C

Air Hoist:

Ingersoll Rand K6U

Pipe Spinner:

Gray Mark 20

Wireline Machine:

Millennium Surveyor

Mud/Gas Separator:

4 X 20

EDR:

MD Totco

TOP DRIVE:

NOV TDS-11, 500 ton

HYDRAULIC CATWALK:

Canrig PC3000

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Requested

OPTIONAL EQUIPMENT:

1 – NOV Hydraulic Rig Walking System X
& Y