



Rig 729 Inventory

(Nomac Rig 29)

DRAWWORKS:

National 610-UE 750 HP
Powered by (1) GE 752 motor

AUXILIARY BRAKE:

Baylor 19RD130W

MAST:

Dreco 142'
572,000 lbs SHL on 10 lines

SUBSTRUCTURE:

Dreco Slingshot w/ 22' floor height
600,000 lbs rotary w/ 360,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK HOOK:
Ideco UTB-265-5-42, 265 ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Ross Hill 3 x 4 SCR Model 1400
Highline Power Capabilities

ENGINE/GENERATORS:

3 - Caterpillar 3508B / Kato 902kW
generators

MUD PUMPS:

2 - National Oilwell 10-P-130, 1300 HP
Each powered by (1) GE 752 motor

MUD SYSTEM:

2 tank, 1000 Bbl w/ 100 Bbl pre-mix
included

SOLIDS CONTROL EQUIPMENT:

SHAKERS:
2 - Mi Swaco Mongoose PT

DEGASSER:
National D-1000-C

DESANDER:
National DSN-2H-10CTX

DESILTER:
National DSLR-16GG-4CTX

BOP EQUIPMENT:

ANNULAR:
Hydril Type GK 11" – 5K WP

DOUBLE:

Church Energy Type U 11" – 5K WP

CHOKE MANIFOLD:

4" x 4" 5000 PSI

CLOSING UNIT:

Advanced Pressure 6 station, 200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:
2 - 500 Bbl each

Fuel Tank:
14,000 gallons

Trip Tank:
100 Bbl

Hyd. Hoist:
1 - Braden PD12C

Air Hoist:
1 - Ingersoll Rand K5UL

Pipe Spinner:
Gray Mark 20

Wireline Machine:
Millennium surveyor

EDR:
MD Totco

TOP DRIVE:
NOV – TDS 11 500 Ton

TUBULARS:
Drill Pipe: 18,000' 5"
Drill Collars: As Requested