



Rig 755 Inventory

(Nomac Rig 55)

DRAWWORKS:

National 80-UE 1000 HP
Powered by (2) GE 752 motors

AUXILIARY BRAKE:

Baylor 6032

MAST:

Dreco 142'
750,000 LB SHL on 12 lines

SUBSTRUCTURE:

Dreco box-on-box
2-box w/ 21' floor height
750,000 lbs rotary w/ 450,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK HOOK:
National Oilwell 650G500 Combo

ROTARY TABLE:

National Oilwell C-275

SCR SYSTEM:

Ross Hill 3 x 4 Model 1400
Highline Power Capabilities

ENGINE/GENERATORS:

3 - Caterpillar 3512C / Kato generators
1365kW

MUD PUMPS:

2 - LeTourneau WH-1612, 1600 HP, 7500 PSI
Each powered by (1) GE 752 traction motors

MUD SYSTEM:

2 tank, 1000 Bbl w/ 100 Bbl pre-mix included

SOLIDS CONTROL EQUIPMENT:

SHAKERS: 2 - Mi Swaco Mongoose PT

DEGASSER:

National D-1000-C

DESANDER:

National DSN-2V-CTX

DESILTER:

National DSLR16GG-4CTX

TOP DRIVE:

NOV TDS-11 - 500 ton

BOP EQUIPMENT:

ANNULAR:
Shaffer Style Spherical 13-5/8" -5K WP

DOUBLE:

Cameron Type U 13-5/8" – 10K WP

SINGLE:

Cameron Type U 13-5/8" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

Advanced Pressure 6 station, 200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:
500 Bbl

Fuel Tank:
14,000 gallons

Trip Tank:
100 Bbl

Hyd. Hoists:
2 - Braden PD12C

Air Hoist:
Ram K6U

Pipe Spinner:
Gray Mark 20

Wireline Machine:
Millennium Surveyor

EDR:
MD Totco

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Required

HYDRAULIC CATWALK:

Forum Wrangler 3550

OPTIONAL EQUIPMENT:

Rig Walking System available
Capabilities: 60'