



Rig 759 Inventory

(Nomac Rig 59)

DRAWWORKS:

National 80-UE 1000 HP
Powered by (2) GE 752 motors

AUXILIARY BRAKE:

Baylor 6032

MAST:

Dreco 142'
750,000 lbs SHL on 12 lines

SUBSTRUCTURE:

Dreco Box-on-Box
2-box w/ 21' floor height
750,000 lbs rotary w/ 450,000 lbs setback

TRAVELING EQUIPMENT:

BLOCK HOOK:
National Oilwell B650GA500, 500ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Ross Hill 3 x 4 SCR Model 1400
Highline Power Capabilities

ENGINE/GENERATORS:

3 - Caterpillar 3512C / Kato 1365kW
generators

MUD PUMPS:

2 - LeTourneau WH-1612, 1600 HP, **7500 PSI**
Each powered by (2) GE 752 motors

MUD SYSTEM:

3 tank, 1000 Bbl w/ 100 Bbl pre-mix
included

SOLIDS CONTROL EQUIPMENT:

SHAKERS:
2 - Brandt King Cobra Venom

DEGASSER:

National DG-ATM

DESANDER:

National DSN-2H-10TX

DESILTER:

National DSLR-16GG-4CTX

OPTIONAL EQUIPMENT:

Rig Walking System available
Capabilities: 120'

BOP EQUIPMENT:

ANNULAR:
Shaffer Style Spherical 13-5/8" – 5K WP

DOUBLE:

Cameron Type U 13-5/8" – 10K WP

SINGLE:

Cameron Type U 13-5/8" – 10K WP

CHOKE MANIFOLD:

4" x 3" 10000 PSI

CLOSING UNIT:

Advanced Pressure 6 station, 200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:
Varco ST-80C

Water Tank:

500 Bbl

Fuel Tank:

14,000 gallons

Trip Tank:

100 Bbl

Hyd. Hoist:

2 - Braden PD12C

Air Hoist:

1 - Ingersoll Rand K6U
1 - Ingersoll Rand HU-40

Pipe Spinner:

Gray Mark 20

Wireline Machine:

Millennium Surveyor

EDR:

MD Totco

Hydraulic Catwalk:

Forum 3550

TOP DRIVE:

NOV TDS-11, 500 ton

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Required