



Rig 765 Inventory

(Nomac Rig 135)

DRAWWORKS:

National 80-UE 1000 HP
Powered by (2) GE 752 motors

AUXILIARY BRAKE:

Baylor 6032

MAST:

Drilling Structures, Inc. 142'
750,000 lbs SHL 12 lines

SUBSTRUCTURE:

Drilling Structures, Inc. Box-on-Box
2-box w/ 20' floor height

TRAVELING EQUIPMENT:

BLOCK: Emsco R44, 350 ton

HOOK:

BJ 6350, 350 ton

ROTARY TABLE:

National Oilwell C-275

DRIVE SYSTEM:

Omron 3 x 4 SCR

ENGINE/GENERATORS:

3 - Caterpillar 3512C / Kato 1365kW
generators

MUD PUMPS:

2 - Emsco FB1600 type, 1600 HP
Each powered by (2) GE 752 motors

MUD SYSTEM:

2 tank, 1050 Bbl w/ 100 Bbl pre-mix
included
w/ pit roofs

SOLIDS CONTROL EQUIPMENT:

SHAKERS:

2 - Derrick FLC-503

DEGASSER:

Derrick VacuFlo 500

DESANDER:

Derrick 2 Cone

DESILTER:

Derrick 12 Cone

BOP EQUIPMENT:

ANNULAR:

Shaffer Style Spherical 11" – 5K WP

DOUBLE:

Cameron Type U 11" – 10K WP

SINGLE:

Cameron Type U 11" – 10K WP

CHOKE MANIFOLD:

4" x 4" 5000 PSI

CLOSING UNIT:

Advanced Pressure 6 station, 200 gallon

AUXILIARY EQUIPMENT:

Iron Roughneck:

Varco ST-80C

Water Tank:

430 Bbl

Fuel Tank:

12,000 gallons

Trip Tank:

100 Bbl

Air Hoists:

1 - Ingersoll Rand K5UL
1 - Ingersoll Rand HU-40

Pipe Spinner:

Oil Works 35C-7

Wireline Machine:

Five Star

EDR:

MD Totco

TOP DRIVE:

NOV TDS-11, 500 ton

MULTI-WELL PAD SITE:

Beam Rail Skidding System
Capabilities: 120'

TUBULARS:

Drill Pipe: 18,000' 5"
Drill Collars: As Required